

- LEGEND**
- PROPOSED STAGE BOUNDARY
  - - - - -42.0- - - - - PROPOSED SURFACE CONTOUR
  - - - - -42.0- - - - - EXISTING SURFACE CONTOUR PREDEVELOPMENT
  - - - - - PROPOSED EARTHWORKS PAD SETBACK LINE
  - - - - - PROPOSED CONCRETE SLEEPER RETAINING WALL
  - - - - - EXISTING CONCRETE SLEEPER RETAINING WALL
  - 42.00 EXISTING SURFACE LEVEL (FSL)
  - 42.00 PROPOSED FINISHED SURFACE LEVEL (FSL) (INCLUDES TOPSOIL PLACEMENT)
  - █ PROPOSED AREA OF CUT GREATER THAN 25mm
  - █ PROPOSED AREA OF FILL GREATER THAN 25mm
  - ▲ INDICATIVE DRIVEWAY LOCATIONS
  - ZERO LOT BOUNDARY
  - - - - - EXISTING STORMWATER DRAINAGE PIPE
  - - - - - EXISTING SEWERAGE MAIN
  - - - - - EXISTING WATER MAIN
  - - - - - EXISTING ELECTRICAL CABLE U/G
  - - - - - EXISTING ELECTRICAL CABLE O/H
  - - - - - EXISTING TELECOMMUNICATION CABLE U/G
  - - - - - EXISTING GAS MAIN
  - - - - - EXISTING TELECOMMUNICATION CABLE O/H
  - EXISTING TREE TO REMAIN - REFER VMP
  - EXISTING TREE TO BE REMOVED - REFER VMP

EXISTING BOREHOLE NS433  
 E:478541.043  
 N:6940440.520  
 CONTRACTOR TO EXCAVATE,  
 REHABILITATION, AND CAP EXISTING BORES  
 IN ACCORDANCE WITH THE REQUIREMENTS  
 OF THE GEOTECHNICAL REPORT

**EXISTING SURFACE NOTE**  
 EXISTING SURFACE BASED ON STAGE 1  
 BULK EARTHWORKS (17-0191), RIPLEY ROAD  
 STAGE 1 WORKS AND EXISTING SURVEY

**WARNING! - EXISTING SERVICES**  
 EXTREME CARE SHOULD BE TAKEN WHEN EXCAVATING IN THIS  
 AREA. THE FOLLOWING EXISTING SERVICES ARE LIKELY TO BE  
 PRESENT IN THE VICINITY OF THE SITE:

- ELECTRICAL CABLES
- TELECOMMUNICATIONS CABLES
- GAS MAINS
- WATER MAINS
- SEWER MAINS


THE CONTRACTOR SHOULD CONTACT THE SERVICE PROVIDER  
 FOR FURTHER INFORMATION AND SATISFY THEMSELVES OF  
 ANY SPECIFIC TREATMENT OR REQUIREMENTS.

REV	DATE	DESIGN	DRAWN	REVISION DETAILS
1	27.04.20	AS	AS	FOR APPROVAL
2	16.06.20	AS	AS	FOR APPROVAL

**NOT FOR CONSTRUCTION**

AS  
 DESIGN APPROVED  
 ANDREW NGO  
 RPEQ 12329

MH  
 FOR AND ON BEHALF OF PEAKURBAN PTY LTD



CLIENT  
**RIPLEY PROJECTS PTY LTD**

ASSOCIATED CONSULTANT  
 SURVEYOR: SURVEY MARK  
 PH: (07) 3188 9020


PROJECT NAME  
**HAYFIELD STAGE 5**

352 RIPLEY ROAD  
 RIPLEY


DRAWING TITLE		
<b>BULK EARTHWORKS LAYOUT PLAN</b>		
PROJECT No. <b>17-0195</b>	DRAWING No. <b>102</b>	REVISION <b>2</b>




SECTION A  
SCALE 1:100 (A1)  
SCALE 1:200 (A3)




TYPICAL STEP BETWEEN LOTS  
(0.00m - 0.50m MAX)  
1:50 (A1)  
1:100 (A3)



SECTION B  
SCALE 1:100 (A1)  
SCALE 1:200 (A3)



SECTION C  
SCALE 1:100 (A1)  
SCALE 1:200 (A3)



CONCRETE SLEEPER RETAINING WALL  
TYPICAL DETAIL  
SCALE 1:25 (A1)

**RETAINING WALL NOTES:**


- ALL RETAINING WALLS ARE TO BE DELIVERED UNDER DESIGN AND CONSTRUCTION ARRANGEMENT - FORMS 15 AND 16 CERTIFICATIONS ARE TO BE PROVIDED BY THE CONTRACTOR.
- BUILDING APPROVAL TO BE OBTAINED FOR ALL RELEVANT RETAINING WALLS, PRIOR TO CONSTRUCTING RETAINING WALLS
- DESIGN OF WALLS TO CONSIDER ALL LOADS (FENCES, DWELLINGS ETC) AND ASSOCIATED IMPACTS FROM ANY ADJACENT SERVICES - FOOTING DEPTHS TO BE EXTENDED AS REQUIRED.
- GEOTECHNICAL CONDITIONS ARE TO BE CONFIRMED AND APPROPRIATELY CONSIDERED FOR ALL WALLS.
- REFER LANDSCAPE DRAWINGS FOR FURTHER INFORMATION ON RETAINING WALLS, PARTICULARLY RELATING TO FINISHES.
- TEMPORARY SAFETY FENCING TO BE INSTALLED BEHIND ALL WALLS 1.0m HIGH AND GREATER.
- CONCRETE SLEEPER RETAINING WALLS ON COMMON BOUNDARY OF ALLOTMENTS AND ROAD RESERVE / OPEN SPACE WHICH ARE VISIBLE FROM PUBLIC SPACE ARE TO BE FINISHED TO FULL DEPTH COLOUR (COFFEE BROWN, TERRACOTTA OR STORM GREY) AND TEXTURED TREATMENT (TIMBER, OR STONE PROFILE AND GRAIN)

**EXISTING BOLEHOLES NOTE:**

CONTRACTOR TO EXCAVATE, REHABILITATE AND CAP EXISTING BOREHOLES WITH GEOMEMBRANE BARRIER IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.

REV	DATE	DESIGN	DRAWN	REVISION DETAILS
1	27.04.20	AS	AS	FOR APPROVAL
2	16.06.20	AS	AS	FOR APPROVAL

DRAWN	STATUS
AS	<b>NOT FOR CONSTRUCTION</b>
DESIGN	APPROVED ANDREW NGO RPEQ 12329
MH	FOR AND ON BEHALF OF PEAKURBAN PTY LTD




CLIENT  
**RIPLEY PROJECTS PTY LTD**

ASSOCIATED CONSULTANT  
SURVEYOR: SURVEY MARK  
PH: (07) 3188 9020

PROJECT NAME  
**HAYFIELD STAGE 5**

352 RIPLEY ROAD  
RIPLEY

DRAWING TITLE		
<b>BULK EARTHWORKS TYPICAL SECTIONS</b>		
PROJECT No.	DRAWING No.	REVISION
17-0195	103	2



**LEGEND**

- PROPOSED AREA OF WORKS
- PROPOSED ROAD CONTROL LINE
- EXISTING ROAD CROWN
- PROPOSED KERB INVERT LINE
- PROPOSED EDGE OF BITUMEN
- EXISTING EDGE OF BITUMEN
- PROPOSED KERB TRANSITION LOCATION
- PROPOSED CONCRETE PATH AND PRAM RAMP
- PROPOSED NEW ROAD PAVEMENT
- INDICATIVE DRIVEWAY LOCATION
- ZERO LOT BOUNDARY
- PROPOSED SURFACE CONTOUR
- EXISTING SURFACE CONTOUR
- PROPOSED STORMWATER DRAINAGE PIPE
- EXISTING STORMWATER DRAINAGE PIPE
- PROPOSED DRAINAGE SWALE
- EXISTING DRAIN
- PROPOSED ROOFWATER KERB ADAPTOR
- PROPOSED ROOFWATER KERB ADAPTOR WITH PIPE CONNECTION TO ALLOTMENT
- PROPOSED AREA OF FILTER MEDIA
- PROPOSED CONCRETE SLEEPER RETAINING WALL
- EXISTING CONCRETE SLEEPER RETAINING WALL
- PROPOSED SEWERAGE MAIN
- EXISTING SEWERAGE MAIN
- PROPOSED WATER MAIN
- EXISTING WATER MAIN
- PROPOSED WATER CONDUIT
- EXISTING WATER CONDUIT
- EXISTING ELECTRICAL CABLE U/G
- EXISTING ELECTRICAL CABLE O/H
- EXISTING TELECOMMUNICATION CABLE U/G
- EXISTING TELECOMMUNICATION CABLE O/H
- EXISTING FIBRE OPTIC CABLE U/G
- EXISTING GAS MAIN
- EXISTING TREE TO REMAIN - REFER VMP
- EXISTING TREE TO BE REMOVED - REFER VMP

**KERB TYPES NOTE:**  
REFER TO THE SURVEY SETOUT ENGINEERING DRAWING FOR KERB TYPES AND TRANSITION LOCATIONS

**ROOFWATER CONNECTION NOTE:**  
THE CONTRACTOR SHALL INSTALL A ROOFWATER CONNECTION TO EACH PROPERTY BY ONE OF THE FOLLOWING METHODS, AS SHOWN ON THE LAYOUT PLAN:

- TWO ROOFWATER KERB ADAPTOR 500mm FROM THE DOWNSTREAM BOUNDARY (UNLESS SHOWN ON A DIFFERENT ALIGNMENT). WHERE THERE IS A CONCRETE FOOTPATH, A ROOFWATER PIPE SHALL BE INSTALLED FROM THE PROPERTY BOUNDARY CONNECTED TO THE KERB ADAPTOR AT 1.25% MINIMUM GRADE, IN ACCORDANCE WITH THE LOCAL AUTHORITY STANDARDS.
- ONE 150Ø ROOFWATER PIPE CONNECTED TO PROPOSED STORMWATER GULLY PIT OR MANHOLE AT MINIMUM 1.0% GRADE WITH 1.0m COVER.

**WARNING! - EXISTING SERVICES**  
EXTREME CARE SHOULD BE TAKEN WHEN EXCAVATING IN THIS AREA. THE FOLLOWING EXISTING SERVICES ARE LIKELY TO BE PRESENT IN THE VICINITY OF THE SITE:

- ELECTRICAL CABLES
- TELECOMMUNICATIONS CABLES
- GAS MAINS
- WATER MAINS
- SEWER MAINS


THE CONTRACTOR SHOULD CONTACT THE SERVICE PROVIDER FOR FURTHER INFORMATION AND SATISFY THEMSELVES OF ANY SPECIFIC TREATMENT OR REQUIREMENTS.

REV	DATE	DESIGN	DRAWN	REVISION DETAILS
1	27.04.20	AS	AS	FOR APPROVAL
2	16.06.20	AS	AS	FOR APPROVAL

**NOT FOR CONSTRUCTION**

AS  
DESIGN APPROVED  
ANDREW NGO  
RPEQ 12329

MH  
FOR AND ON BEHALF OF PEAKURBAN PTY LTD



CLIENT  
**RIPLEY PROJECTS PTY LTD**

ASSOCIATED CONSULTANT  
SURVEYOR: SURVEY MARK  
PH: (07) 3188 9020

PROJECT NAME  
**HAYFIELD STAGE 5**

352 RIPLEY ROAD  
RIPLEY

DRAWING TITLE		
<b>ROADWORKS AND DRAINAGE LAYOUT PLAN</b>		
PROJECT No.	DRAWING No.	REVISION
17-0195	104	2



**LEGEND**

- PROPOSED AREA OF WORKS/STAGE BOUNDARY
- PROPOSED NEW ROAD PAVEMENT
- PROPOSED ROAD CONTROL LINE
- PROPOSED MOUNTABLE KERB AND CHANNEL TYPE M1
- PROPOSED MOUNTABLE KERB AND CHANNEL TYPE B1
- PROPOSED CONCRETE PATH AND PRAM RAMP
- INDICATIVE DRIVEWAY LOCATION
- ZERO LOT BOUNDARY
- KERB TRANSITION

**CONTROL LINE SETOUT - POLLEN STREET**

PT	CHAINAGE	EASTING	NORTHING	BEARING
IP 1	0.000	478397.879	6940481.064	170°04'39.06"
IP 2	76.750	478411.104	6940405.462	170°04'39.06"

**CONTROL LINE SETOUT - BASIN DRIVEWAY**

PT	CHAINAGE	EASTING	NORTHING	BEARING	RAD/SPIRAL	A.LENGTH	DEFL.ANGLE
IP 1	0.000	478539.926	6940406.712	71°15'15.41"			
TC	3.090	478542.853	6940407.705	71°15'15.41"			
IP 2	12.206	478551.889	6940410.772		R = -25.000	18.231	41°46'58.79"
CT	21.322	478556.584	6940419.080	29°28'16.62"			
IP 3	27.458	478559.603	6940424.422	29°28'16.62"			

**CONTROL LINE SETOUT - ROAD 12**

PT	CHAINAGE	EASTING	NORTHING	BEARING	RAD/SPIRAL	A.LENGTH	DEFL.ANGLE
IP 1	0.000	478411.104	6940405.462	260°04'39.16"			
TC	54.998	478356.929	6940395.985	260°04'39.16"			
IP 2	65.155	478343.136	6940393.572		R = -11.500	20.314	101°12'29.30"
CT	75.311	478348.184	6940380.511	158°52'09.86"			
TC	104.778	478358.806	6940353.026	158°52'09.86"			
IP 3	106.270	478359.344	6940351.634		R = 100.000	2.984	1°42'35.25"
CT	107.762	478359.840	6940350.227	160°34'45.11"			
TC	200.593	478390.707	6940262.678	160°34'45.11"			
IP 4	207.818	478393.577	6940254.536		R = -10.500	14.451	78°51'10.37"
CT	215.044	478402.120	6940255.778	81°43'34.74"			
TC	301.899	478488.072	6940268.277	81°43'34.74"			
IP 5	307.112	478493.582	6940269.078		R = -12.000	10.427	49°47'12.51"
CT	312.326	478496.528	6940273.804	31°56'22.23"			
TC	339.891	478511.111	6940297.196	31°56'22.23"			
IP 6	343.591	478513.072	6940300.342		R = -48.250	7.400	8°47'12.64"
CT	347.291	478514.529	6940303.750	23°09'09.59"			
TC	359.585	478519.363	6940315.054	23°09'09.59"			
IP 7	371.070	478523.899	6940325.661		R = -100.000	22.970	13°09'39.05"
CT	382.555	478525.900	6940337.022	9°59'30.54"			
TC	444.727	478536.688	6940398.251	9°59'30.54"			
IP 8	457.917	478539.922	6940416.606		R = -14.500	26.379	104°14'03.26"
CT	471.106	478521.335	6940415.227	265°45'27.29"			
TC	561.615	478431.074	6940408.532	265°45'27.29"			
IP 9	565.828	478426.869	6940408.220		R = -85.000	8.426	5°40'47.87"
CT	570.041	478422.716	6940407.493	260°04'39.42"			
IP 10	581.829	478411.104	6940405.462	260°04'39.42"			

**CONTROL LINE SETOUT - ROAD 13**

PT	CHAINAGE	EASTING	NORTHING	BEARING	RAD/SPIRAL	A.LENGTH	DEFL.ANGLE
IP 1	0.000	478370.977	6940318.640	70°34'44.40"			
TC	10.289	478380.681	6940322.061	70°34'44.40"			
IP 2	12.776	478383.031	6940322.889		R = 30.000	4.973	9°29'54.76"
CT	15.263	478385.486	6940323.319	80°04'39.16"			
TC	63.389	478432.892	6940331.612	80°04'39.16"			
IP 3	66.858	478436.313	6940332.210		R = 70.000	6.939	5°40'48.20"
CT	70.328	478439.776	6940332.467	85°45'27.36"			
TC	133.032	478502.308	6940337.106	85°45'27.36"			
IP 4	137.591	478506.891	6940337.446		R = 30.000	9.119	17°25'00.74"
CT	142.151	478511.365	6940336.398	103°10'28.11"			
IP 5	156.291	478525.133	6940333.176	103°10'28.11"			

REV	DATE	DESIGN	DRAWN	REVISION DETAILS
1	27.04.20	AS	AS	FOR APPROVAL
2	16.06.20	AS	AS	FOR APPROVAL


**NOT FOR CONSTRUCTION**

DESIGN APPROVED: ANDREW NGO RPEQ 12329

DRAWN: AS

DRAWN: MH

FOR AND ON BEHALF OF PEAKURBAN PTY LTD



CLIENT: RIPLEY PROJECTS PTY LTD

ASSOCIATED CONSULTANT: SURVEYOR: SURVEY MARK PH: (07) 3188 9020

PROJECT NAME: HAYFIELD STAGE 5

352 RIPLEY ROAD RIPLEY


DRAWING TITLE: SURVEY SETOUT AND KERB TYPES LAYOUT PLAN

PROJECT No.	DRAWING No.	REVISION
17-0195	105	2

ASSUMED PAVEMENT DETAILS (SUBJECT TO CBR TESTING)

ROAD	ROAD CLASSIFICATION	DESIGN ESAs	ASSUMED CBR	SURFACING	BASE	SUB BASE	LOWER SUB BASE	TOTAL DEPTH
ROAD 12	ACCESS STREET	1.0 x 10 <sup>5</sup>	3	35mm	125mm	100mm	150mm	410mm

NOTE: THIS PAVEMENT DESIGN IS PRELIMINARY ONLY BASED ON AN ASSUMED CBR. THE CONTRACTOR SHALL SUPPLY THE SUPERINTENDENT WITH SUBGRADE TEST RESULTS NECESSARY FOR FINAL PAVEMENT DESIGN



DATUM RL 27.0



CHAINAGES	EXISTING SURFACE	DESIGN SURFACE	RHS LIP LEVEL	LHS LIP LEVEL	CUT (-) / FILL	HORIZONTAL CURVES
0.000	50.390	50.390	#	50.278	0.000	
20.000	51.490	51.484	51.372	51.372	-0.007	
40.000	52.591	52.577	52.465	52.465	-0.113	
45.056	52.868	52.854	52.742	52.742	-0.115	
54.998	53.344	53.333	53.221	53.205	-0.111	
60.000	53.516	53.525	53.413	53.374	0.009	
75.311	53.884	53.910	53.799	53.762	0.026	
80.000	53.937	53.967	53.855	53.855	0.030	
86.922	53.962	53.998	53.887	53.887	0.036	
90.056	53.954	53.992	53.880	53.880	0.038	
100.000	53.847	53.887	53.775	53.775	0.039	
104.778	53.763	53.790	53.678	53.678	0.037	
107.762	53.681	53.715	53.603	53.603	0.034	
120.000	53.276	53.284	53.172	53.172	0.008	
135.056	52.483	52.485	52.373	#	0.002	
140.000	52.191	52.174	52.063	#	-0.017	
154.247	51.348	51.279	51.167	#	-0.070	
160.000	51.008	50.928	50.816	#	-0.080	
169.247	50.461	50.409	50.297	50.297	-0.053	
180.000	49.973	49.875	49.763	49.763	-0.098	
184.247	49.739	49.684	49.573	49.573	-0.055	
195.120	49.142	49.212	49.100	49.100	0.070	
200.000	48.874	48.995	48.883	48.874	0.121	
200.593	48.841	48.967	48.856	48.842	0.126	
210.120	48.435	48.508	48.396	48.365	0.074	
215.044	48.147	48.254	48.142	48.128	0.107	
220.000	47.981	47.987	47.875	47.875	0.006	
225.120	47.711	47.699	47.692	47.587	-0.012	
240.000	46.865	46.844	46.737	46.732	-0.021	
260.000	45.728	45.695	45.588	45.583	-0.034	
269.869	45.167	45.128	45.021	45.016	-0.040	
280.000	44.634	44.599	44.493	44.488	-0.035	
294.869	44.044	44.019	43.913	43.907	-0.025	
300.000	43.893	43.873	43.766	43.761	-0.020	
301.899	43.841	43.825	43.719	43.709	-0.015	
312.326	43.642	43.634	43.527	43.517	-0.008	
319.869	43.567	43.566	43.460	43.455	-0.001	
320.000	43.566	43.566	43.459	43.454	-0.000	
339.891	43.463	43.467	43.360	43.355	0.003	
340.000	43.463	43.466	43.359	43.354	0.003	
347.291	43.425	43.430	43.323	43.318	0.005	
359.585	43.385	43.368	43.262	43.257	0.004	
360.000	43.362	43.366	43.260	43.254	0.004	
380.000	43.261	43.266	43.160	#	0.006	
382.555	43.251	43.254	43.147	#	0.003	
400.000	43.167	43.167	43.060	43.055	-0.000	
420.000	43.067	43.067	42.961	42.955	-0.000	
430.557	43.014	43.014	42.908	42.903	-0.000	
433.064	43.008	43.008	42.802	42.896	-0.000	
440.000	43.057	43.056	42.949	42.944	-0.001	
444.727	43.143	43.143	43.037	43.024	0.001	
445.557	43.160	43.163	43.057	43.040	0.003	
460.000	43.688	43.730	43.623	43.581	0.042	
460.557	43.714	43.760	43.648	43.611	0.046	
471.106	44.296	44.336	44.225	44.217	0.040	
480.000	44.788	44.823	44.711	44.711	0.035	
500.000	45.888	45.916	45.804	45.804	0.028	
520.000	46.988	47.010	46.898	46.898	0.021	
540.000	48.089	48.103	47.991	47.991	0.014	
560.000	49.189	49.197	49.085	49.085	0.007	
561.615	49.278	49.285	49.173	49.173	0.007	
570.041	49.741	49.746	49.634	49.634	0.004	
580.000	50.288	50.290	50.178	50.178	0.001	
581.829	50.390	50.390	50.278	50.278	-0.000	

ROAD 12

<table border="1"> <thead> <tr> <th>REV</th> <th>DATE</th> <th>DESIGN</th> <th>DRAWN</th> <th>REVISION DETAILS</th> </tr> </thead> <tbody> <tr> <td>1</td> <td>27.04.20</td> <td>AS</td> <td>AS</td> <td>FOR APPROVAL</td> </tr> <tr> <td>2</td> <td>16.06.20</td> <td>AS</td> <td>AS</td> <td>FOR APPROVAL</td> </tr> </tbody> </table>	REV	DATE	DESIGN	DRAWN	REVISION DETAILS	1	27.04.20	AS	AS	FOR APPROVAL	2	16.06.20	AS	AS	FOR APPROVAL	<table border="1"> <thead> <tr> <th>DRAWN</th> <th>STATUS</th> </tr> </thead> <tbody> <tr> <td>AS</td> <td>NOT FOR CONSTRUCTION</td> </tr> </tbody> </table>	DRAWN	STATUS	AS	NOT FOR CONSTRUCTION	<p><b>PEAKURBAN</b> DEVELOPMENT ENGINEERS + ADVISORS</p> <p>ENQUIRIES@PEAKURBAN.COM.AU</p>	<p>SCALE</p> <p>1:1000 10 0 10 20 30 40 50 A1 1:2000 HORIZONTAL A3</p> <p>1:100 2 1 0 2 4 A1 1:200 VERTICAL A3</p>	<p>CLIENT</p> <p><b>RIPLEY PROJECTS PTY LTD</b></p> <p>ASSOCIATED CONSULTANT SURVEYOR: SURVEY MARK PH: (07) 3188 9020</p>	<p>PROJECT NAME</p> <p><b>HAYFIELD STAGE 5</b></p> <p>352 RIPLEY ROAD RIPLEY</p>	<p>DRAWING TITLE</p> <p><b>ROAD 12 LONGITUDINAL SECTION</b></p> <p>PROJECT No. <b>17-0195</b> DRAWING No. <b>106</b> REVISION <b>2</b></p>
REV	DATE	DESIGN	DRAWN	REVISION DETAILS																					
1	27.04.20	AS	AS	FOR APPROVAL																					
2	16.06.20	AS	AS	FOR APPROVAL																					
DRAWN	STATUS																								
AS	NOT FOR CONSTRUCTION																								

(EW) REFER TO BULK EARTHWORKS DRAWING FOR LOT GRADING AND FINISHED SURFACE LEVELS

- INTERSECTION ROAD 13 -



REV	DATE	DESIGN	DRAWN	REVISION DETAILS
1	27.04.20	AS	AS	FOR APPROVAL
2	16.06.20	AS	AS	FOR APPROVAL


**NOT FOR CONSTRUCTION**

AS

DESIGN APPROVED ANDREW NGO RPEQ 12329

MH

FOR AND ON BEHALF OF PEAKURBAN PTY LTD



CLIENT

**RIPLEY PROJECTS PTY LTD**

ASSOCIATED CONSULTANT

SURVEYOR: SURVEY MARK  
PH: (07) 3188 9020

PROJECT NAME



**HAYFIELD STAGE 5**

352 RIPLEY ROAD  
RIPLEY

DRAWING TITLE		
<b>ROAD 12 CROSS SECTIONS SHEET 1 OF 3</b>		
PROJECT No.	DRAWING No.	REVISION
17-0195	107	2



(EW) REFER TO BULK EARTHWORKS DRAWING FOR LOT GRADING AND FINISHED SURFACE LEVELS



REV	DATE	DESIGN	DRAWN	REVISION DETAILS
1	27.04.20	AS	AS	FOR APPROVAL
2	16.06.20	AS	AS	FOR APPROVAL


**NOT FOR CONSTRUCTION**

DRAWN: AS

DESIGN: APPROVED ANDREW NGO RPEQ 12329

MH

FOR AND ON BEHALF OF PEAKURBAN PTY LTD



CLIENT: RIPLEY PROJECTS PTY LTD

ASSOCIATED CONSULTANT: SURVEYOR: SURVEY MARK PH: (07) 3188 9020

PROJECT NAME: HAYFIELD STAGE 5

352 RIPLEY ROAD RIPLEY



DRAWING TITLE: ROAD 12 CROSS SECTIONS SHEET 2 OF 3

PROJECT No: 17-0195

DRAWING No: 108

REVISION: 2


(EW) REFER TO BULK EARTHWORKS DRAWING FOR LOT GRADING AND FINISHED SURFACE LEVELS



REV	DATE	DESIGN	DRAWN	REVISION DETAILS
1	27.04.20	AS	AS	FOR APPROVAL
2	16.06.20	AS	AS	FOR APPROVAL

DRAWN	STATUS	<p align="center"><b>NOT FOR CONSTRUCTION</b></p>
AS		
DESIGN	APPROVED	<p align="center">RPEQ 12329</p>
MH	ANDREW NGO	
FOR AND ON BEHALF OF PEAKURBAN PTY LTD		

  
 DEVELOPMENT ENGINEERS • ADVISORS  
 ENQUIRIES@PEAKURBAN.COM.AU



CLIENT

**RIPLEY PROJECTS PTY LTD**

ASSOCIATED CONSULTANT  
SURVEYOR: SURVEY MARK  
PH: (07) 3188 9020

PROJECT NAME

**HAYFIELD STAGE 5**

352 RIPLEY ROAD  
RIPLEY


DRAWING TITLE		
<b>ROAD 12 CROSS SECTIONS SHEET 3 OF 3</b>		
PROJECT No.	DRAWING No.	REVISION
17-0195	109	2

ASSUMED PAVEMENT DETAILS (SUBJECT TO CBR TESTING)

ROAD	ROAD CLASSIFICATION	DESIGN ESAs	ASSUMED CBR	SURFACING	BASE	SUB BASE	LOWER SUB BASE	TOTAL DEPTH
ROAD 13	ACCESS STREET	1.0 x 10 <sup>5</sup>	3	35mm	125mm	100mm	150mm	410mm


(EW) REFER TO BULK EARTHWORKS DRAWING FOR LOT GRADING AND FINISHED SURFACE LEVELS

NOTE: THIS PAVEMENT DESIGN IS PRELIMINARY ONLY BASED ON AN ASSUMED CBR. THE CONTRACTOR SHALL SUPPLY THE SUPERINTENDENT WITH SUBGRADE TEST RESULTS NECESSARY FOR FINAL PAVEMENT DESIGN



DATUM RL 28.0			
CUT (-) / FILL		-0.022	0.006
LHS LIP LEVEL	#	50.748	49.904
RHS LIP LEVEL	#	49.239	48.886
DESIGN SURFACE		52.095	51.246
EXISTING SURFACE		51.117	51.272
CHAINAGES		0.000	80.000
HORIZONTAL CURVES		R30.000	R70.000

ROAD 13  
# REFER INTERSECTION DRAWINGS FOR LIP LEVELS



REV	DATE	DESIGN	DRAWN	REVISION DETAILS
1	27.04.20	AS	AS	FOR APPROVAL
2	16.06.20	AS	AS	FOR APPROVAL

DRAWN STATUS  
**AS**

DESIGN APPROVED  
ANDREW NGO RPEQ 12329

MH

FOR AND ON BEHALF OF PEAKURBAN PTY LTD

**NOT FOR CONSTRUCTION**

**PEAKURBAN**  
DEVELOPMENT ENGINEERS + ADVISORS

ENQUIRIES@PEAKURBAN.COM.AU

SCALE

1:100 1 2 3 4 5 A1  
1:200 1 2 3 4 5 A3

1:1000 10 20 30 40 50 A1  
1:2000 10 20 30 40 50 A3

1:100 1 2 3 4 5 A1  
1:200 1 2 3 4 5 A3

HORIZONTAL  
VERTICAL

CLIENT  
**RIPLEY PROJECTS PTY LTD**

ASSOCIATED CONSULTANT  
SURVEYOR: SURVEY MARK  
PH: (07) 3188 9020


PROJECT NAME  
**HAYFIELD STAGE 5**

352 RIPLEY ROAD  
RIPLEY

DRAWING TITLE  
**ROAD 13 LONGITUDINAL SECTION AND CROSS SECTIONS 1 OF 2**


PROJECT No. **17-0195**  
DRAWING No. **110**  
REVISION **2**

(EW) REFER TO BULK EARTHWORKS DRAWING FOR LOT GRADING AND FINISHED SURFACE LEVELS



REV	DATE	DESIGN	DRAWN	REVISION DETAILS
1	27.04.20	AS	AS	FOR APPROVAL
2	16.06.20	AS	AS	FOR APPROVAL

DRAWN	STATUS	<p align="center"><b>NOT FOR CONSTRUCTION</b></p>
AS		
DESIGN	APPROVED	<p align="center">RPEQ 12329</p>
MH	ANDREW NGO	
FOR AND ON BEHALF OF PEAKURBAN PTY LTD		



CLIENT	PROJECT NAME
RIPLEY PROJECTS PTY LTD	HAYFIELD STAGE 5
ASSOCIATED CONSULTANT	352 RIPLEY ROAD RIPLEY
SURVEYOR: SURVEY MARK PH: (07) 3188 9020	


DRAWING TITLE
ROAD 13 LONGITUDINAL SECTION AND CROSS SECTIONS 2 OF 2
PROJECT No. 17-0195
DRAWING No. 111
REVISION 2

ASSUMED PAVEMENT DETAILS (SUBJECT TO CBR TESTING)

ROAD	ROAD CLASSIFICATION	DESIGN ESAs	ASSUMED CBR	SURFACING	BASE	SUB BASE	LOWER SUB BASE	TOTAL DEPTH
POLLEN STREET	ACCESS STREET	1.0 x 10 <sup>5</sup>	3	35mm	125mm	100mm	150	410mm


(EW) REFER TO BULK EARTHWORKS DRAWING FOR LOT GRADING AND FINISHED SURFACE LEVELS

NOTE: THIS PAVEMENT DESIGN IS PRELIMINARY ONLY BASED ON AN ASSUMED CBR. THE CONTRACTOR SHALL SUPPLY THE SUPERINTENDENT WITH SUBGRADE TEST RESULTS NECESSARY FOR FINAL PAVEMENT DESIGN



	0.000	13.000	18.000	20.000	20.938	23.000	40.000	60.000	66.000	71.000	71.740	76.750
DATUM RL 32.0												
CUT (-) / FILL	0.004	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.005	-0.011	-0.018
LHS LIP LEVEL							49.858	50.014				
RHS LIP LEVEL							49.858	50.014				
DESIGN SURFACE	50.338	49.948	49.845	49.831	49.829	49.837	49.969	50.125	50.133	50.177	50.230	50.389
EXISTING SURFACE	50.354	49.948	49.845	49.831	49.829	49.837	49.969	50.125	50.133	50.177	50.230	50.389
CHAINAGES	0.000	13.000	18.000	20.000	20.938	23.000	40.000	60.000	66.000	71.000	71.740	76.750
HORIZONTAL CURVES												


POLLEN STREET  
# REFER INTERSECTION DRAWINGS FOR LIP LEVELS



REV	DATE	DESIGN	DRAWN	REVISION DETAILS
1	27.04.20	AS	AS	FOR APPROVAL
2	16.06.20	AS	AS	FOR APPROVAL

DRAWN	STATUS
AS	NOT FOR CONSTRUCTION
MH	DESIGN APPROVED ANDREW NGO RPEQ 12329

**PEAKURBAN**  
DEVELOPMENT ENGINEERS • ADVISORS  
ENQUIRIES@PEAKURBAN.COM.AU




CLIENT  
**RIPLEY PROJECTS PTY LTD**

ASSOCIATED CONSULTANT  
SURVEYOR: SURVEY MARK  
PH: (07) 3188 9020

PROJECT NAME  
**HAYFIELD STAGE 5**


352 RIPLEY ROAD  
RIPLEY

DRAWING TITLE		
<b>POLLEN STREET LONGITUDINAL SECTION AND CROSS SECTIONS</b>		
PROJECT No.	DRAWING No.	REVISION
17-0195	112	2



DATUM RL 25.0	
CUT (-) / FILL	-0.010 0.278 0.433 0.641 0.799 0.952 0.478 0.216 -0.913
DESIGN SURFACE	43.212 43.368 43.405 43.454 43.401 43.224 42.996 42.193 41.000
EXISTING SURFACE	43.222 43.090 42.972 42.813 42.603 42.172 42.021 41.977 41.963 41.913
CHAINAGES	0.000 1.250 3.090 5.541 8.091 13.091 18.091 20.000 21.322 27.458
HORIZONTAL CURVES	R-25.000

BASIN ACCESS DRIVEWAY



**NOTE: #**  
DRIVEWAY CROSSOVER GRADES AND SETOUT TO BE IN ACCORDANCE WITH ICC STD DRG SR.13 (UNO)

**DRIVEWAY CONCRETE NOTES:**  
• CONCRETE ASSESS RAMP GENERALLY IN ACCORDANCE WITH I.C.C STD. DRG. SR.17

REV	DATE	DESIGN	DRAWN	REVISION DETAILS
1	27.04.20	AS	AS	FOR APPROVAL
2	16.06.20	AS	AS	FOR APPROVAL

DRAWN	STATUS
AS	<b>NOT FOR CONSTRUCTION</b>
DESIGN	APPROVED ANDREW NGO RPEQ 12329
MH	

**PEAKURBAN**  
DEVELOPMENT ENGINEERS • ADVISORS

ENQUIRIES@PEAKURBAN.COM.AU

SCALE

1:100 1 0 1 2 3 4 5 A1

1:200 1 0 1 2 3 4 5 A3

1:1000 10 0 10 20 30 40 50 A1

1:2000 10 0 10 20 30 40 50 A3

1:100 1 0 1 2 3 4 5 A1

1:200 1 0 1 2 3 4 5 A3

GROSS SECTIONS

HORIZONTAL

VERTICAL

CLIENT

**RIPLEY PROJECTS PTY LTD**

ASSOCIATED CONSULTANT

SURVEYOR: SURVEY MARK  
PH: (07) 3188 9020

PROJECT NAME

**HAYFIELD STAGE 5**

352 RIPLEY ROAD  
RIPLEY






DRAWING TITLE

**BASIN ACCESS DRIVEWAY LONGITUDINAL AND CROSS SECTIONS**

PROJECT No. **17-0195**

DRAWING No. **113**

REVISION **2**



- LEGEND**
- PROPOSED ROAD CONTROL LINE
  - PROPOSED KERB INVERT LINE
  - PROPOSED KERB SETOUT NODE
  - PROPOSED CONCRETE PATH AND PRAM RAMP
  - ▲ INDICATIVE DRIVEWAY LOCATION
  - - - - -41.0- - - - - PROPOSED PAVEMENT CONTOUR (0.1m INTERVAL)
  - - - - - PROPOSED STORMWATER DRAINAGE PIPE
  - - - - - PROPOSED SEWER MAIN
  - - - - - PROPOSED WATER MAIN
  - - - - - EXISTING SEWER MAIN
  - - - - - EXISTING WATER MAIN
  - PROPOSED KERB SETOUT LINE
  - SP PROPOSED KERB SETOUT START POINT
  - EP PROPOSED KERB SETOUT END POINT
  - - - - - PROPOSED ROAD CUTBACK LINE
  - - - - - EXISTING EDGE OF BITUMEN

ALL KERB RETURN AND PAVEMENT WIDENING REFERENCE THE LIP OF KERB UNLESS NOTED OTHERWISE

**ROAD WIDENING SETOUT**

NUMBER	EASTING	NORTHING
1	478360.869	6940392.893
2	478352.865	6940378.731
3	478393.195	6940266.824
4	478404.636	6940259.908
5	478485.469	6940271.663
6	478494.472	6940277.547
7	478532.573	6940396.366
8	478519.047	6940411.322

REV	DATE	DESIGN	DRAWN	REVISION DETAILS
1	27.04.20	AS	AS	FOR APPROVAL
2	16.06.20	AS	AS	FOR APPROVAL

**NOT FOR CONSTRUCTION**

AS

DESIGN APPROVED ANDREW NGO RPEQ 12329

MH

FOR AND ON BEHALF OF PEAKURBAN PTY LTD

**PEAKURBAN**

DEVELOPMENT ENGINEERS • ADVISORS

ENQUIRIES@PEAKURBAN.COM.AU

SCALE

1:250 5 0 5 10 A1

1:500

CLIENT

**RIPLEY PROJECTS PTY LTD**

ASSOCIATED CONSULTANT

SURVEYOR: SURVEY MARK

PH: (07) 3188 9020

PROJECT NAME

**HAYFIELD STAGE 5**




352 RIPLEY ROAD

RIPLEY

DRAWING TITLE



**INTERSECTION DETAILS LAYOUT PLAN SHEET 1 OF 2**

PROJECT No.	DRAWING No.	REVISION
17-0195	114	2



ALL KERB RETURN AND PAVEMENT WIDENING REFERENCE THE LIP OF KERB UNLESS NOTED OTHERWISE

REFER SHEET 114 FOR LEGEND



**DRIVEWAY 01 DETAILS**  
SCALE 1:100 (A1)  
SCALE 1:200 (A3)

**DRIVEWAY 01 SETOUT**

POINT	EASTING	NORTHING
21	478399.203	6940251.738
22	478398.152	6940246.575
23	478398.729	6940241.393
24	478398.969	6940240.861
25	478396.233	6940239.630
26	478395.993	6940240.163
27	478395.213	6940247.174
28	478395.875	6940250.429
29	478396.263	6940252.336

REV	DATE	DESIGN	DRAWN	REVISION DETAILS
1	27.04.20	AS	AS	FOR APPROVAL
2	16.06.20	AS	AS	FOR APPROVAL

**NOT FOR CONSTRUCTION**


DRAWN: AS

DESIGN: MH

APPROVED: ANDREW NGO

RPEQ 12329

FOR AND ON BEHALF OF PEAKURBAN PTY LTD



CLIENT: RIPLEY PROJECTS PTY LTD

ASSOCIATED CONSULTANT: SURVEYOR: SURVEY MARK  
PH: (07) 3188 9020


PROJECT NAME: HAYFIELD STAGE 5

352 RIPLEY ROAD RIPLEY

DRAWING TITLE: INTERSECTION DETAILS LAYOUT PLAN SHEET 2 OF 2

PROJECT No.	DRAWING No.	REVISION
17-0195	115	2






DATUM RL 48.0

LIP LEVEL	NORTHING	EASTING	CHAINAGES	HORIZONTAL CURVES
51.030	6940406.762	478396.918	0.000	R-10.025
50.842	6940407.710	478399.752	3.000	
50.755	6940408.343	478400.822	4.244	
50.625	6940409.452	478402.181	6.000	
50.422	6940411.388	478403.731	8.487	
50.380	6940411.832	478403.989	9.000	
50.179	6940414.639	478405.014	12.000	
50.143	6940415.360	478405.133	12.731	
50.061	6940417.624	478405.166	15.000	
50.044	6940418.364	478405.065	15.747	
50.027	6940419.573	478404.854	16.975	


KR1



DATUM RL 47.0

LIP LEVEL	NORTHING	EASTING	CHAINAGES	HORIZONTAL CURVES
50.021	6940421.699	478412.045	0.000	R-10.275
50.022	6940421.497	478412.080	0.205	
50.029	6940420.199	478412.314	1.564	
50.030	6940419.654	478412.416	2.078	
50.028	6940418.766	478412.660	3.000	
49.998	6940415.086	478413.984	6.000	
49.964	6940414.770	478415.066	7.705	
49.930	6940413.900	478416.024	9.000	
49.825	6940412.395	478416.606	12.000	
49.682	6940411.696	478421.513	15.000	
49.671	6940411.690	478421.717	15.205	
49.518	6940411.683	478423.196	16.665	
49.518	6940411.780	478424.507	18.000	
49.354	6940412.002	478427.499	21.000	
49.190	6940412.224	478430.491	24.000	
49.173			24.309	


KR2



DATUM RL 49.0

LIP LEVEL	NORTHING	EASTING	CHAINAGES	HORIZONTAL CURVES
52.779	6940332.273	478370.120	0.000	R-9.275
52.560	6940329.653	478371.554	3.000	
52.536	6940329.452	478371.715	3.258	
52.229	6940327.624	478373.746	6.000	
52.160	6940327.351	478374.184	6.516	
51.852	6940326.397	478376.469	9.000	
51.768	6940326.229	478377.224	9.774	
51.560	6940326.100	478379.441	12.000	
51.480	6940326.221	478380.465	13.032	
51.336	6940326.560	478382.404	15.000	
51.178			17.182	


KR3



DATUM RL 49.0

LIP LEVEL	NORTHING	EASTING	CHAINAGES	HORIZONTAL CURVES
51.090	6940319.786	478386.906	0.000	R-10.025
51.304	6940318.838	478384.072	3.000	
51.366	6940318.143	478382.913	4.352	
51.413	6940317.096	478381.643	6.000	
51.429	6940315.866	478380.569	7.635	
51.422	6940314.973	478379.981	8.705	
51.418	6940314.716	478379.835	9.000	
51.350	6940311.908	478378.810	12.000	
51.314	6940310.864	478378.654	13.057	
51.231	6940308.923	478378.658	15.000	
51.098	6940306.577	478379.179	17.409	


KR4



DATUM RL 41.0

LIP LEVEL	NORTHING	EASTING	CHAINAGES	HORIZONTAL CURVES
42.968	6940340.155	478511.658	0.000	R-10.275
42.992	6940339.905	478514.636	3.000	
43.003	6940340.045	478515.905	4.178	
43.023	6940340.522	478517.561	6.000	
43.053	6940341.584	478519.658	8.355	
43.061	6940341.955	478520.185	9.000	
43.087	6940344.083	478522.285	12.000	
43.089	6940344.521	478522.569	12.533	
43.093	6940346.209	478523.485	14.448	
43.093	6940346.725	478523.683	15.000	
43.088	6940348.377	478524.119	16.711	

KR5



DATUM RL 41.0

LIP LEVEL	NORTHING	EASTING	CHAINAGES	HORIZONTAL CURVES
43.244	6940318.984	478516.950	0.000	R-10.275
43.219	6940321.774	478517.713	3.000	
43.199	6940323.254	478517.772	4.482	
43.174	6940324.762	478517.611	6.000	
43.109	6940327.563	478516.671	8.965	
43.109	6940327.594	478516.655	9.000	
43.043	6940330.031	478514.923	12.000	
43.017	6940331.002	478513.852	13.447	
42.995	6940331.866	478512.563	15.000	
42.929	6940332.929	478509.844	17.929	

KR6

REV	DATE	DESIGN	DRAWN	REVISION DETAILS
1	27.04.20	AS	AS	FOR APPROVAL
2	16.06.20	AS	AS	FOR APPROVAL

DRAWN STATUS  
**AS**  
 DESIGN APPROVED ANDREW NGO RPEQ 12329  
 MH  
 FOR AND ON BEHALF OF PEAKURBAN PTY LTD

**NOT FOR CONSTRUCTION**  
  
 DEVELOPMENT ENGINEERS • ADVISORS  
 ENQUIRIES@PEAKURBAN.COM.AU

SCALE  
 1:250 5 0 5 10 A1  
 1:500 HORIZONTAL  
 1:25 0 0.25 0.5 0.75 1 1.25 A1  
 1:50 VERTICAL

CLIENT  
**RIPLEY PROJECTS PTY LTD**  
 ASSOCIATED CONSULTANT  
 SURVEYOR: SURVEY MARK  
 PH: (07) 3188 9020

PROJECT NAME  
**HAYFIELD STAGE 5**  
 352 RIPLEY ROAD  
 RIPLEY

DRAWING TITLE  
**INTERSECTION KERB RETURN LONGITUDINAL SECTIONS**  
 PROJECT No. **17-0195**  
 DRAWING No. **116**  
 REVISION **2**



LEGEND	
	PROPOSED AREA OF WORKS
	PROPOSED SINGLE STREET NAME SIGN
	EXISTING SINGLE STREET NAME SIGN
	PROPOSED ROAD SIGN
	EXISTING ROAD SIGN
	UDL
	PROPOSED UNBROKEN DIVIDING LINE
	PROPOSED RRPM - WHITE - BIDIRECTIONAL
	EXISTING LINEMARKING (LINETYPES AS PER PROPOSED)
	INDICATIVE DRIVEWAY LOCATION

**GENERAL NOTES**

- ALL EXISTING SIGNAGE AND LINEMARKING TO REMAIN UNO.
- ALL PROPOSED SIGNAGE AND LINEMARKING SHALL BE IN ACCORDANCE WITH I.C.C STANDARDS AND THE QUEENSLAND GOVERNMENT'S MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES.

REV	DATE	DESIGN	DRAWN	REVISION DETAILS
1	27.04.20	AS	AS	FOR APPROVAL
2	16.06.20	AS	AS	FOR APPROVAL


**NOT FOR CONSTRUCTION**

DESIGN APPROVED  
ANDREW NGO

MH

RPEQ 12329

FOR AND ON BEHALF OF PEAKURBAN PTY LTD



CLIENT

**RIPLEY PROJECTS PTY LTD**


ASSOCIATED CONSULTANT  
SURVEYOR: SURVEY MARK  
PH: (07) 3188 9020

PROJECT NAME

**HAYFIELD STAGE 5**

352 RIPLEY ROAD  
RIPLEY

DRAWING TITLE		
<b>SIGNS AND LINEMARKING LAYOUT PLAN</b>		
PROJECT No.	DRAWING No.	REVISION
17-0195	117	2



**LEGEND**

- 1 CATCHMENT NAME
- CATCHMENT BOUNDARY
- PROPOSED STORMWATER DRAINAGE PIPE
- EXISTING STORMWATER DRAINAGE PIPE
- PROPOSED ROOFWATER DRAINAGE PIPE
- PROPOSED SWALE DRAIN
- PROPOSED CONTOUR
- EXISTING CONTOUR

**CATCHMENT AREAS**

CATCHMENT	AREA (ha)
G9/1	0.143
G8/1	0.291
G7/1	0.169
G6/1	0.326
G5/1	0.079
G4/1	0.136
G3/1	0.054
G2/1	0.151
C5/2	0.171
G4/2	0.249
G3/2	0.206
G2/2	0.244
G1/2	0.066
G1/3	0.190
G1/4	0.247
G3/5	0.317
G2/5	0.222
G1/5	0.231
G1/6	0.217
IN/7	0.234

REV	DATE	DESIGN	DRAWN	REVISION DETAILS
1	27.04.20	AS	AS	FOR APPROVAL
2	16.06.20	AS	AS	FOR APPROVAL

DRAWN	STATUS	<b>NOT FOR CONSTRUCTION</b>	
AS			
DESIGN	APPROVED		
MH	ANDREW NGO	RPEQ 12329	
<small>FOR AND ON BEHALF OF PEAKURBAN PTY LTD</small>			

**PEAKURBAN**  
DEVELOPMENT ENGINEERS • ADVISORS

ENQUIRIES@PEAKURBAN.COM.AU

SCALE

1:500 10 5 0 10 20 A1  
1:1000

CLIENT

**RIPLEY PROJECTS PTY LTD**

ASSOCIATED CONSULTANT  
SURVEYOR: SURVEY MARK  
PH: (07) 3188 9020

PROJECT NAME

**HAYFIELD STAGE 5**

352 RIPLEY ROAD  
RIPLEY

DRAWING TITLE

**STORMWATER DRAINAGE CATCHMENT LAYOUT PLAN**

PROJECT No.	DRAWING No.	REVISION
17-0195	118	2


STRUCTURE NAME	G9/1	G8/1	G7/1	G6/1	G5/1	G4/1	G3/1	G2/1	1/1	OUT/1
STRUCTURE DESCRIPTION	LIP IN LINE GULLY PIT 2.4m LINTEL, ON-GRADE	STD GULLY PIT WITH 1050mm MANHOLE - LIP IN LINE 2.4m LINTEL, ON-GRADE	STD GULLY PIT - LIP IN LINE 2.4m LINTEL, ON-GRADE	STD GULLY PIT - LIP IN LINE 2.4m LINTEL, ON-GRADE	STD GULLY PIT - LIP IN LINE 2.4m LINTEL, ON-GRADE	STD GULLY PIT WITH 1050mm MANHOLE - LIP IN LINE 2.4m LINTEL, ON-GRADE	STD GULLY PIT WITH 2100mm MANHOLE - LIP IN LINE 2.4m LINTEL, ON-GRADE REFER TO DETAIL ON 17-0195-122	STD GULLY PIT WITH 1500mm MANHOLE - LIP IN LINE 2.4m LINTEL, SAG	CUSTOM MANHOLE REFER TO DETAIL ON 17-0195-122	CONCRETE HEADWALL

**STORMWATER STRUCTURE NOTE:**  
 STANDARD ROUND MANHOLES LESS THAN 3.0m DEEP:  
 CONSTRUCT IN ACCORDANCE WITH THE LOCAL AUTHORITY STANDARDS.  
 STANDARD ROUND MANHOLES 3.0m > 5.3m DEEP:  
 CONSTRUCT IN ACCORDANCE WITH TMR STD DRAWINGS 1307 AND 1308.  
 STANDARD ROUND MANHOLES GREATER THAN 5.3m DEEP:  
 SHALL BE STRUCTURALLY DESIGNED (CERTIFIED) AND CONSTRUCTED BY CONTRACTOR ON A CASE BY CASE BASIS.  
 ROUND EXTENDED (900mm MAX) MANHOLES:  
 CONSTRUCT IN ACCORDANCE WITH PEAK URBAN STD DRAWINGS S-101 & S-102.  
 RECTANGULAR STRUCTURE (SPECIAL):  
 SHALL BE STRUCTURALLY DESIGNED (CERTIFIED) AND CONSTRUCTED BY CONTRACTOR ON A CASE BY CASE BASIS.

PIPE SIZE (mm)	375	375	375	525	525	600	825	825	(2x)750	(2x)450	375	375	375	375	450	
PIPE CLASS	3	3	3	3	3	3	4	4	3	3	3	3	3	3	3	
PIPE GRADE (%)	5.70%	2.77%	5.01%	2.41%	0.35%	0.35%	0.20%	0.20%	0.50%	0.75%	5.02%	5.30%	4.97%	5.27%	4.16%	
PIPE SLOPE (1 in X)	17.54	36.12	19.97	41.43	284.84	284.83	500.00	500.00	200.00	132.64	19.94	18.86	20.14	18.98	24.05	
FULL PIPE VELOCITY (m/s)	0.39	1.01	1.54	1.08	1.26	1.17	1.22	1.48	0.58	1.82	0.44	1.00	1.45	2.06	2.05	
PART FULL VELOCITY (m/s)	2.45	2.46	3.43	2.81	1.32	1.46	1.37	1.48	1.59	1.82	2.42	3.11	3.36	3.76	3.76	
DATUM RL	34.0															
H.G.L IN PIPE & W.S.E IN STRUCTURE	52.056 52.000	47.518 47.541 47.325	46.921 46.975 46.698	43.342 43.286 43.226	43.155 43.183 42.994	42.810 42.830 42.708	42.639 42.663 42.463	42.361 42.387 42.221	42.102 42.105 42.061	42.050 42.050 42.050	49.896 49.800	48.647 48.673 48.522	46.271 46.321 46.078	45.201 45.254 44.852	43.363 43.426 42.950	42.102 42.109 42.061
PIPE FLOW (Cumeecs)	0.043	0.111	0.170	0.233	0.272	0.330	0.653	0.792	0.511	0.580	0.049	0.110	0.160	0.228	0.325	
PIPE CAPACITY AT GRADE (Cumeecs)	0.419	0.292	0.393	0.668	0.255	0.364	0.642	0.642	1.581	0.495	0.393	0.404	0.391	0.403	0.582	
DEPTH TO INVERT	1.485	1.820 1.840	1.417 1.438	1.110 1.379	1.327 1.347	1.298 1.373	1.330 1.350	2.164 2.444	0.661 0.661	2.226	1.472	1.424 1.483	1.428 1.472	1.424 1.487	1.432 1.877	2.164 2.444
INVERT LEVEL OF DRAIN	51.850	47.100 47.080	46.416 46.395	43.169 42.900	42.130 42.110	41.948 41.873	41.535 41.515	41.450 41.170	41.068 41.068	41.430	49.640	48.337 48.278	45.828 45.784	44.575 44.512	43.001 42.556	41.450 41.170
DESIGN SURFACE LEVEL	53.335	48.920	47.833	44.279	43.457	43.246	42.866	43.614	41.729	43.656	51.112	49.761	47.256	45.999	44.433	43.614
SETOUT COORDINATES	E 478398.583 N 6940341.764	E 478398.284 N 6940263.192	E 478407.781 N 6940262.560	E 478469.888 N 6940269.675	E 478501.472 N 6940274.173	E 478516.176 N 6940317.911	E 478538.532 N 6940385.666	E 478543.113 N 6940417.783	E 478563.217 N 6940414.374	E 478563.946 N 6940425.542	E 478394.945 N 6940406.696	E 478420.670 N 6940403.075	E 478465.297 N 6940415.081	E 478468.818 N 6940408.804	E 478517.415 N 6940410.922	E 478543.113 N 6940417.783
RUNNING CHAINAGE	0.000	83.313	107.295	171.717	31.902	203.619	46.144	249.763	23.641	49.309	322.712	32.442	355.154	20.390	375.544	

LINE 1


STRUCTURE NAME	1/1	OUT/1A
STRUCTURE DESCRIPTION	CUSTOM MANHOLE REFER TO DETAIL ON 17-0195-122	CONCRETE HEADWALL REFER TO DETAIL ON 17-0195-122



PIPE SIZE (mm)	(2x)450
PIPE CLASS	3
PIPE GRADE (%)	0.75%
PIPE SLOPE (1 in X)	132.64
FULL PIPE VELOCITY (m/s)	1.82
PART FULL VELOCITY (m/s)	1.82
DATUM RL	28.0
H.G.L IN PIPE & W.S.E IN STRUCTURE	41.865 41.865 41.711 41.711
PIPE FLOW (Cumeecs)	0.580
PIPE CAPACITY AT GRADE (Cumeecs)	0.495
DEPTH TO INVERT	2.226
INVERT LEVEL OF DRAIN	41.430
DESIGN SURFACE LEVEL	43.656
SETOUT COORDINATES	E 478563.946 N 6940425.542
RUNNING CHAINAGE	12.601 12.601

1A

STRUCTURE NAME	G5/2	G4/2	G3/2	G2/2	G1/2	1/1
STRUCTURE DESCRIPTION	LIP IN LINE GULLY PIT 2.4m LINTEL, ON-GRADE	LIP IN LINE GULLY PIT 2.4m LINTEL, ON-GRADE	LIP IN LINE GULLY PIT 2.4m LINTEL, ON-GRADE	LIP IN LINE GULLY PIT 2.4m LINTEL, ON-GRADE	STD GULLY PIT WITH 1050mm MANHOLE - LIP IN LINE 2.4m LINTEL, ON-GRADE	CUSTOM MANHOLE REFER TO DETAIL ON 17-0195-122



PIPE SIZE (mm)	375	375	375	375	450	
PIPE CLASS	3	3	3	3	3	
PIPE GRADE (%)	5.02%	5.30%	4.97%	5.27%	4.16%	
PIPE SLOPE (1 in X)	19.94	18.86	20.14	18.98	24.05	
FULL PIPE VELOCITY (m/s)	0.44	1.00	1.45	2.06	2.05	
PART FULL VELOCITY (m/s)	2.42	3.11	3.36	3.76	3.76	
DATUM RL	33.0					
H.G.L IN PIPE & W.S.E IN STRUCTURE	49.896 49.800	48.647 48.673 48.522	46.271 46.321 46.078	45.201 45.254 44.852	43.363 43.426 42.950	42.102 42.109 42.061
PIPE FLOW (Cumeecs)	0.049	0.110	0.160	0.228	0.325	
PIPE CAPACITY AT GRADE (Cumeecs)	0.393	0.404	0.391	0.403	0.582	
DEPTH TO INVERT	1.472	1.424 1.483	1.428 1.472	1.424 1.487	1.432 1.877	2.164 2.444
INVERT LEVEL OF DRAIN	49.640	48.337 48.278	45.828 45.784	44.575 44.512	43.001 42.556	41.450 41.170
DESIGN SURFACE LEVEL	51.112	49.761	47.256	45.999	44.433	43.614
SETOUT COORDINATES	E 478394.945 N 6940406.696	E 478420.670 N 6940403.075	E 478465.297 N 6940415.081	E 478468.818 N 6940408.804	E 478517.415 N 6940410.922	E 478543.113 N 6940417.783
RUNNING CHAINAGE	0.000	25.979	46.214	72.193	24.345	26.598


2

<table border="1"> <tr> <th>REV</th> <th>DATE</th> <th>DESIGN</th> <th>DRAWN</th> <th>REVISION DETAILS</th> </tr> <tr> <td>1</td> <td>27.04.20</td> <td>AS</td> <td>AS</td> <td>FOR APPROVAL</td> </tr> <tr> <td>2</td> <td>16.06.20</td> <td>AS</td> <td>AS</td> <td>FOR APPROVAL</td> </tr> </table>	REV	DATE	DESIGN	DRAWN	REVISION DETAILS	1	27.04.20	AS	AS	FOR APPROVAL	2	16.06.20	AS	AS	FOR APPROVAL	<table border="1"> <tr> <th>DRAWN</th> <th>STATUS</th> </tr> <tr> <td>AS</td> <td>NOT FOR CONSTRUCTION</td> </tr> <tr> <td>MH</td> <td>APPROVED ANDREW NGO RPEQ 12329</td> </tr> </table>	DRAWN	STATUS	AS	NOT FOR CONSTRUCTION	MH	APPROVED ANDREW NGO RPEQ 12329	<p>DEVELOPMENT ENGINEERS • ADVISORS</p> <p>ENQUIRIES@PEAKURBAN.COM.AU</p>	<p>SCALE</p> <p>1:1000 10 0 10 20 30 40 50 A1</p> <p>1:2000 HORIZONTAL A3</p> <p>1:100 2 1 0 2 4 A1</p> <p>1:200 VERTICAL A3</p>	<p>CLIENT</p> <p><b>RIPLEY PROJECTS PTY LTD</b></p> <p>ASSOCIATED CONSULTANT</p> <p>SURVEYOR: SURVEY MARK PH: (07) 3188 9020</p>	<p>PROJECT NAME</p> <p><b>HAYFIELD STAGE 5</b></p> <p>352 RIPLEY ROAD RIPLEY</p>	<p>DRAWING TITLE</p> <p><b>STORMWATER DRAINAGE LONGITUDINAL SECTIONS SHEET 1 OF 2</b></p> <p>PROJECT No. <b>17-0195</b></p> <p>DRAWING No. <b>119</b></p> <p>REVISION <b>2</b></p>
REV	DATE	DESIGN	DRAWN	REVISION DETAILS																							
1	27.04.20	AS	AS	FOR APPROVAL																							
2	16.06.20	AS	AS	FOR APPROVAL																							
DRAWN	STATUS																										
AS	NOT FOR CONSTRUCTION																										
MH	APPROVED ANDREW NGO RPEQ 12329																										

STRUCTURE NAME	G1/3	G1/2
STRUCTURE DESCRIPTION	LIP IN LINE GULLY PIT 2.4m LINTEL, ON-GRADE	LIP IN LINE 2.4m LINTEL, ON-GRADE


**STORMWATER STRUCTURE NOTE:**  
 STANDARD ROUND MANHOLES LESS THAN 3.0m DEEP:  
 CONSTRUCT IN ACCORDANCE WITH THE LOCAL AUTHORITY STANDARDS.  
 STANDARD ROUND MANHOLES 3.0m > 5.3m DEEP:  
 CONSTRUCT IN ACCORDANCE WITH TMR STD DRAWINGS 1307 AND 1308.  
 STANDARD ROUND MANHOLES GREATER THAN 5.3m DEEP:  
 SHALL BE STRUCTURALLY DESIGNED (CERTIFIED) AND CONSTRUCTED BY CONTRACTOR ON A CASE BY CASE BASIS.  
 RECTANGULAR STRUCTURE (SPECIAL):  
 SHALL BE STRUCTURALLY DESIGNED (CERTIFIED) AND CONSTRUCTED BY CONTRACTOR ON A CASE BY CASE BASIS.

PIPE SIZE (mm)	375
PIPE CLASS	3
PIPE GRADE (%)	2.01%
PIPE SLOPE (1 in X)	49.72
FULL PIPE VELOCITY (m/s)	0.54
PART FULL VELOCITY (m/s)	1.85
DATUM RL	31.0
H.G.L IN PIPE & W.S.E IN STRUCTURE	43.518 43.372 43.363 43.426 42.950
PIPE FLOW (Cumecs)	0.060
PIPE CAPACITY AT GRADE (Cumecs)	0.249
DEPTH TO INVERT	1.431 1.600 1.877
INVERT LEVEL OF DRAIN	42.994 42.833 42.956
DESIGN SURFACE LEVEL	44.425 44.433
SETOUT COORDINATES	E 478516.927 N 6940418.911 E 478517.415 N 6940410.922
RUNNING CHAINAGE	0.000 8.004 8.004



LINE	3
------	---


STRUCTURE NAME	G1/4	G2/1
STRUCTURE DESCRIPTION	STD GULLY PIT - LIP IN LINE 2.4m LINTEL, SAG	STD GULLY PIT WITH 1500mm MANHOLE - LIP IN LINE 2.4m LINTEL, SAG



PIPE SIZE (mm)	450
PIPE CLASS	3
PIPE GRADE (%)	2.00%
PIPE SLOPE (1 in X)	50.00
FULL PIPE VELOCITY (m/s)	0.57
PART FULL VELOCITY (m/s)	2.04
DATUM RL	29.0
H.G.L IN PIPE & W.S.E IN STRUCTURE	42.513 42.369 42.361 42.387 42.221
PIPE FLOW (Cumecs)	0.090
PIPE CAPACITY AT GRADE (Cumecs)	0.403
DEPTH TO INVERT	1.113 1.266 1.350
INVERT LEVEL OF DRAIN	41.759 41.599 41.515
DESIGN SURFACE LEVEL	42.872
SETOUT COORDINATES	E 478530.653 N 6940387.054 E 478538.532 N 6940385.666
RUNNING CHAINAGE	0.000 8.000 8.000

LINE	4
------	---


STRUCTURE NAME	G3/5	G2/5	G1/5	G3/1
STRUCTURE DESCRIPTION	LIP IN LINE GULLY PIT 2.4m LINTEL, ON-GRADE	LIP IN LINE GULLY PIT 2.4m LINTEL, ON-GRADE	STD GULLY PIT WITH 1800mm MANHOLE - LIP IN LINE 2.4m LINTEL, SAG REFER TO DETAIL ON 17-0195-122	STD GULLY PIT WITH 2100mm MANHOLE - LIP IN LINE 2.4m LINTEL, ON-GRADE REFER TO DETAIL ON 17-0195-122



PIPE SIZE (mm)	375	375	(2x)525
PIPE CLASS	3	3	3
PIPE GRADE (%)	2.23%	5.91%	0.35%
PIPE SLOPE (1 in X)	44.77	16.91	285.71
FULL PIPE VELOCITY (m/s)	0.65	1.16	0.74
PART FULL VELOCITY (m/s)	2.02	3.37	1.24
DATUM RL	31.0	31.0	31.0
H.G.L IN PIPE & W.S.E IN STRUCTURE	45.805 45.600 45.625 45.640 45.451	42.726 42.730 42.669	42.639 42.663 42.463
PIPE FLOW (Cumecs)	0.072	0.128	0.322
PIPE CAPACITY AT GRADE (Cumecs)	0.262	0.427	0.509
DEPTH TO INVERT	1.444 1.420 1.441	1.185 1.201	1.453 1.473
INVERT LEVEL OF DRAIN	45.404 45.208 45.187	41.744 41.728	41.654 41.634
DESIGN SURFACE LEVEL	46.848	42.929	43.106
SETOUT COORDINATES	E 478447.793 N 6940337.073 E 478451.982 N 6940329.362	E 478509.065 N 6940340.884	E 478529.977 N 6940337.105
RUNNING CHAINAGE	0.000 8.776 8.776	58.234	67.010 21.250 88.260

LINE	5
------	---


STRUCTURE NAME	G1/6	G1/5
STRUCTURE DESCRIPTION	STD GULLY PIT - LIP IN LINE 2.4m LINTEL, SAG	STD GULLY PIT WITH 1800mm MANHOLE - LIP IN LINE 2.4m LINTEL, SAG REFER TO DETAIL ON 17-0195-122



PIPE SIZE (mm)	525
PIPE CLASS	3
PIPE GRADE (%)	0.81%
PIPE SLOPE (1 in X)	123.45
FULL PIPE VELOCITY (m/s)	0.42
PART FULL VELOCITY (m/s)	1.47
DATUM RL	30.0
H.G.L IN PIPE & W.S.E IN STRUCTURE	42.799 42.729 42.726 42.730 42.669
PIPE FLOW (Cumecs)	0.092
PIPE CAPACITY AT GRADE (Cumecs)	0.387
DEPTH TO INVERT	1.126 1.192 1.201
INVERT LEVEL OF DRAIN	41.802 41.737 41.728
DESIGN SURFACE LEVEL	42.928
SETOUT COORDINATES	E 478507.457 N 6940333.022 E 478509.065 N 6940340.884
RUNNING CHAINAGE	0.000 8.024 8.024





LINE	6
------	---

STRUCTURE NAME	IN/7	OUT/7
STRUCTURE DESCRIPTION	FIELD INLET TYPE 1 900x900	CONCRETE HEADWALL



PIPE SIZE (mm)	675
PIPE CLASS	3
PIPE GRADE (%)	0.25%
PIPE SLOPE (1 in X)	200.00
FULL PIPE VELOCITY (m/s)	1.70
PART FULL VELOCITY (m/s)	1.89
DATUM RL	28.0
H.G.L IN PIPE & W.S.E IN STRUCTURE	41.589 41.064 41.000 41.000 41.000
PIPE FLOW (Cumecs)	0.608
PIPE CAPACITY AT GRADE (Cumecs)	0.595
DEPTH TO INVERT	1.301 0.963 0.963
INVERT LEVEL OF DRAIN	39.700 39.670 39.670
DESIGN SURFACE LEVEL	41.300
SETOUT COORDINATES	E 478579.477 N 6940466.531 E 478590.920 N 6940460.874
RUNNING CHAINAGE	0.000 12.240 12.240

LINE	7
------	---



REV	DATE	DESIGN	DRAWN	REVISION DETAILS
1	27.04.20	AS	AS	FOR APPROVAL
2	16.06.20	AS	AS	FOR APPROVAL

DRAWN	STATUS	NOT FOR CONSTRUCTION
AS	APPROVED	RPEQ 12329
MH	ANDREW NGO	





SCALE	1:1000	10 0 10 20 30 40 50	A1
	1:2000		A3
	1:100	2 1 0 2 4	A1
	1:200		A3
	1:50	1 0.5 0 1 2	A1
	1:100		A3

CLIENT	RIPLEY PROJECTS PTY LTD
ASSOCIATED CONSULTANT	SURVEYOR: SURVEY MARK PH: (07) 3188 9020


PROJECT NAME	HAYFIELD STAGE 5
	352 RIPLEY ROAD RIPLEY

DRAWING TITLE	STORMWATER DRAINAGE LONGITUDINAL SECTIONS SHEET 2 OF 2
PROJECT No.	17-0195
DRAWING No.	120
REVISION	2







**1/1 - 2100mm EXTENDED 2700mm SPLITTER MANHOLE**  
 1:20 (A1)  
 1:40 (A3)




**G1/5 - GULLY WITH 1800mm MANHOLE**  
 1:20 (A1)  
 1:40 (A3)



**G3/1 - GULLY WITH 1800mm MANHOLE**  
 1:20 (A1)  
 1:40 (A3)



**1/1 - SECTION A**  
 1:20 (A1)  
 1:40 (A3)



**1/1 - SECTION B**  
 1:20 (A1)  
 1:40 (A3)

REV	DATE	DESIGN	DRAWN	REVISION DETAILS
1	27.04.20	AS	AS	FOR APPROVAL
2	16.06.20	AS	AS	FOR APPROVAL


**NOT FOR CONSTRUCTION**

AS

DESIGN APPROVED ANDREW NGO RPEQ 12329

MH

FOR AND ON BEHALF OF PEAKURBAN PTY LTD



CLIENT

**RIPLEY PROJECTS PTY LTD**

ASSOCIATED CONSULTANT


SURVEYOR: SURVEY MARK  
 PH: (07) 3188 9020

PROJECT NAME

**HAYFIELD STAGE 5**

352 RIPLEY ROAD  
 RIPLEY

DRAWING TITLE		
<b>STORMWATER DRAINAGE STRUCTURE DETAILS</b>		
PROJECT No.	DRAWING No.	REVISION
17-0195	122	2



**WARNING! - EXISTING SERVICES**  
 EXTREME CARE SHOULD BE TAKEN WHEN EXCAVATING IN THIS AREA. THE FOLLOWING EXISTING SERVICES ARE LIKELY TO BE PRESENT IN THE VICINITY OF THE SITE:



- ELECTRICAL CABLES
- TELECOMMUNICATIONS CABLES
- GAS MAINS
- WATER MAINS
- SEWER MAINS

THE CONTRACTOR SHOULD CONTACT THE SERVICE PROVIDER FOR FURTHER INFORMATION AND SATISFY THEMSELVES OF ANY SPECIFIC TREATMENT OR REQUIREMENTS.

- LEGEND**
- AREA OF WORKS
  - FOOTPATH CONTROL LINE
  - PROPOSED KERB INVERT LINE
  - PROPOSED CONCRETE PATH AND PRAM RAMP
  - PROPOSED BATTER LINE
  - PROPOSED HAYFIELD RUNNING TRACK
  - TREES TO BE RETAINED

**CONTROL LINE SETOUT - HAYFIELD RUNNING TRACK**

PT	CHAINAGE	EASTING	NORTHING	BEARING	RAD/SPIRAL	A.LENGTH	DEFL.ANGLE
IP 1	0.000	478538.238	6940424.101	16°00'40.29"			
TC	16.065	478542.669	6940439.543	16°00'40.29"			
IP 2	16.958	478542.916	6940440.404		R = -10.000	1.785	10°13'40.41"
CT	17.850	478543.006	6940441.294	5°46'59.88"			
TC	28.950	478544.124	6940452.338	5°46'59.88"			
IP 3	31.112	478544.343	6940454.493		R = 25.000	4.322	9°54'21.11"
CT	33.273	478544.929	6940456.579	15°41'20.99"			
TC	57.528	478551.488	6940479.931	15°41'20.99"			
IP 4	61.197	478552.625	6940483.980		R = 6.000	7.338	70°04'06.31"
CT	64.866	478556.820	6940484.292	85°45'27.30"			
IP 5	77.000	478568.921	6940485.189				
IP 6	79.500	478568.738	6940487.683	355°47'43.84"			



DATUM RL 27.0

CUT (-) / FILL	0.168	0.081	0.053	0.044	0.045	0.041	0.032	-0.000	-0.004	0.004	0.012	0.008	-0.055	-0.055	0.000	0.012	-0.007	0.005	0.018	-0.001	0.000
DESIGN SURFACE	43.990	44.068	44.112	44.175	44.330	44.381	44.444	44.670	44.705	46.182	46.318	46.359	46.426	46.425	46.392	46.348	45.864	45.769	45.761	45.782	45.799
EXISTING SURFACE	43.822	43.987	44.059	44.131	44.285	44.340	44.412	44.670	44.709	46.178	46.306	46.351	46.481	46.480	46.392	46.337	45.871	45.764	45.744	45.783	45.799
CHAINAGES	0.000	5.725	8.225	10.725	16.065	17.850	20.000	27.792	28.950	57.528	60.000	60.743	63.148	63.243	64.866	65.743	73.853	76.353	77.311	78.853	79.500
HORIZONTAL CURVES					R-10.000			R-10.000	R25.000							R6.000					

<table border="1"> <thead> <tr> <th>REV</th> <th>DATE</th> <th>DESIGN</th> <th>DRAWN</th> <th>REVISION DETAILS</th> </tr> </thead> <tbody> <tr> <td>1</td> <td>27.04.20</td> <td>AS</td> <td>AS</td> <td>FOR APPROVAL</td> </tr> <tr> <td>2</td> <td>16.06.20</td> <td>AS</td> <td>AS</td> <td>FOR APPROVAL</td> </tr> </tbody> </table>	REV	DATE	DESIGN	DRAWN	REVISION DETAILS	1	27.04.20	AS	AS	FOR APPROVAL	2	16.06.20	AS	AS	FOR APPROVAL	<table border="1"> <thead> <tr> <th>DRAWN</th> <th>STATUS</th> </tr> </thead> <tbody> <tr> <td>AS</td> <td>NOT FOR CONSTRUCTION</td> </tr> </tbody> </table>	DRAWN	STATUS	AS	NOT FOR CONSTRUCTION	<p>DEVELOPMENT ENGINEERS • ADVISORS</p> <p>ENQUIRIES@PEAKURBAN.COM.AU</p>	<table border="1"> <thead> <tr> <th>SCALE</th> <th>A1</th> <th>A3</th> </tr> </thead> <tbody> <tr> <td>1:500</td> <td>10</td> <td>20</td> </tr> <tr> <td>1:1000</td> <td>5</td> <td>10</td> </tr> <tr> <td>1:100</td> <td>2</td> <td>4</td> </tr> <tr> <td>1:200</td> <td>1</td> <td>2</td> </tr> <tr> <td>1:250</td> <td>5</td> <td>10</td> </tr> <tr> <td>1:500</td> <td>2</td> <td>4</td> </tr> </tbody> </table>	SCALE	A1	A3	1:500	10	20	1:1000	5	10	1:100	2	4	1:200	1	2	1:250	5	10	1:500	2	4	<table border="1"> <thead> <tr> <th>CLIENT</th> <th>PROJECT NAME</th> </tr> </thead> <tbody> <tr> <td>RIPLEY PROJECTS PTY LTD</td> <td>HAYFIELD STAGE 5</td> </tr> </tbody> </table>	CLIENT	PROJECT NAME	RIPLEY PROJECTS PTY LTD	HAYFIELD STAGE 5	<table border="1"> <thead> <tr> <th>DRAWING TITLE</th> <th>PROJECT No.</th> <th>DRAWING No.</th> <th>REVISION</th> </tr> </thead> <tbody> <tr> <td>HAYFIELD RUNNING TRACK DETAIL AND LAYOUT PLAN</td> <td>17-0195</td> <td>123</td> <td>2</td> </tr> </tbody> </table>	DRAWING TITLE	PROJECT No.	DRAWING No.	REVISION	HAYFIELD RUNNING TRACK DETAIL AND LAYOUT PLAN	17-0195	123	2
REV	DATE	DESIGN	DRAWN	REVISION DETAILS																																																					
1	27.04.20	AS	AS	FOR APPROVAL																																																					
2	16.06.20	AS	AS	FOR APPROVAL																																																					
DRAWN	STATUS																																																								
AS	NOT FOR CONSTRUCTION																																																								
SCALE	A1	A3																																																							
1:500	10	20																																																							
1:1000	5	10																																																							
1:100	2	4																																																							
1:200	1	2																																																							
1:250	5	10																																																							
1:500	2	4																																																							
CLIENT	PROJECT NAME																																																								
RIPLEY PROJECTS PTY LTD	HAYFIELD STAGE 5																																																								
DRAWING TITLE	PROJECT No.	DRAWING No.	REVISION																																																						
HAYFIELD RUNNING TRACK DETAIL AND LAYOUT PLAN	17-0195	123	2																																																						
<table border="1"> <thead> <tr> <th>DESIGN</th> <th>APPROVED</th> <th>FOR AND ON BEHALF OF PEAKURBAN PTY LTD</th> </tr> </thead> <tbody> <tr> <td>MH</td> <td>ANDREW NGO</td> <td>RPEQ 12329</td> </tr> </tbody> </table>		DESIGN	APPROVED	FOR AND ON BEHALF OF PEAKURBAN PTY LTD	MH	ANDREW NGO	RPEQ 12329	<table border="1"> <thead> <tr> <th>ASSOCIATED CONSULTANT</th> <th>SURVEYOR</th> <th>PH: (07) 3188 9020</th> </tr> </thead> <tbody> <tr> <td>SURVEY MARK</td> <td></td> <td></td> </tr> </tbody> </table>		ASSOCIATED CONSULTANT	SURVEYOR	PH: (07) 3188 9020	SURVEY MARK			<table border="1"> <thead> <tr> <th>352 RIPLEY ROAD</th> <th>RIPLEY</th> </tr> </thead> <tbody> <tr> <td></td> <td></td> </tr> </tbody> </table>		352 RIPLEY ROAD	RIPLEY																																						
DESIGN	APPROVED	FOR AND ON BEHALF OF PEAKURBAN PTY LTD																																																							
MH	ANDREW NGO	RPEQ 12329																																																							
ASSOCIATED CONSULTANT	SURVEYOR	PH: (07) 3188 9020																																																							
SURVEY MARK																																																									
352 RIPLEY ROAD	RIPLEY																																																								



**WARNING! - EXISTING SERVICES**

EXTREME CARE SHOULD BE TAKEN WHEN EXCAVATING IN THIS AREA. THE FOLLOWING EXISTING SERVICES ARE LIKELY TO BE PRESENT IN THE VICINITY OF THE SITE:


- ELECTRICAL CABLES
- TELECOMMUNICATIONS CABLES
- GAS MAINS
- WATER MAINS
- SEWER MAINS

THE CONTRACTOR SHOULD CONTACT THE SERVICE PROVIDER FOR FURTHER INFORMATION AND SATISFY THEMSELVES OF ANY SPECIFIC TREATMENT OR REQUIREMENTS.

**LEGEND**

- PROPOSED BATTER LINE
- PROPOSED RETAINING WALL, REFER BULK EARTHWORKS DRAWINGS
- SETOUT POINT
- PROPOSED FINISHED SURFACE LEVEL
- PROPOSED STORMWATER DRAINAGE PIPE
- PROPOSED 100Ø SLOTTED SUB SOIL DRAINAGE PIPE WITH CLEAN-OUT POINT
- PROPOSED 225Ø UN-SLOTTED COLLECTOR PIPE
- PROPOSED BIO RETENTION FILTER AREA
- PROPOSED PLANTED BATTER - BY LANDSCAPERS
- PROPOSED TURFED MAINTENANCE BENCH AND SPILLWAY
- PROPOSED ROCK SCOUR PROTECTION
- PROPOSED LOCKABLE RAIL TO COUNCIL STANDARDS


**NOTE:**  
THE BASIN DRAWINGS ARE TO BE READ IN CONJUNCTION WITH THE LANDSCAPE ARCHITECT'S DRAWINGS AND DOCUMENTATION, SPECIFICALLY RELATING TO RETAINING WALLS, BARRIERS, PLANTING AND VEGETATION




**SETOUT**

POINT	EASTING	NORTHING
01	478555.610	6940427.982
02	478556.121	6940428.423
03	478559.191	6940433.848
04	478560.947	6940440.648
05	478561.444	6940441.889
06	478571.457	6940459.579
07	478573.255	6940460.989
08	478576.897	6940462.015
09	478578.130	6940461.323
10	478579.451	6940456.632
11	478579.266	6940455.105
12	478565.283	6940430.400
13	478561.343	6940423.438
14	478556.750	6940426.037

REV	DATE	DESIGN	DRAWN	REVISION DETAILS	DRAWN	STATUS	SCALE	CLIENT	PROJECT NAME	DRAWING TITLE
1	27.04.20	AS	AS	FOR APPROVAL	AS	NOT FOR CONSTRUCTION	1:100 1:200	RIPLEY PROJECTS PTY LTD	HAYFIELD STAGE 5	BIO RETENTION BASIN LAYOUT PLAN
2	16.06.20	AS	AS	FOR APPROVAL	MH	APPROVED ANDREW NGO RPEQ 12329	1:100 1:200	ASSOCIATED CONSULTANT SURVEYOR: SURVEY MARK PH: (07) 3188 9020	352 RIPLEY ROAD RIPLEY	PROJECT No. 17-0195 DRAWING No. 200 REVISION 2




RL 41.0  
**SECTION A**  
 SCALE 1:100 (A1)  
 SCALE 1:200 (A3)






RL 41.0  
**SECTION B**  
 SCALE 1:100 (A1)  
 SCALE 1:200 (A3)

REV	DATE	DESIGN	DRAWN	REVISION DETAILS	DRAWN	STATUS	SCALE	CLIENT	PROJECT NAME	DRAWING TITLE
1	27.04.20	AS	AS	FOR APPROVAL	AS	<b>NOT FOR CONSTRUCTION</b>	1:100 1:200	RIPLEY PROJECTS PTY LTD	HAYFIELD STAGE 5	BIO RETENTION BASIN TYPICAL SECTIONS
2	16.06.20	AS	AS	FOR APPROVAL						
					MH	APPROVED ANDREW NGO RPEQ 12329	1 0 1 2 3 4 5 A1 2 000 000 A3	ASSOCIATED CONSULTANT SURVEYOR: SURVEY MARK PH: (07) 3188 9020	352 RIPLEY ROAD RIPLEY	PROJECT No. 17-0195 DRAWING No. 201 REVISION 2





**BIO RETENTION FILTER MEDIA AND SUBSOIL DRAINAGE DETAIL**  
 REFERENCE: IPWEA STD DRG DS-073  
 SCALE 1:20 (A1) 1:40 (A3)



- NOTES:**
1. BIORETENTION SYSTEM SURFACE. SURFACE LEVEL IS TOP OF FILTER MEDIA. SURFACE TO BE MULCHED AND PLANTED AS PER PROJECT DRAWINGS AND THE 'BIORETENTION TECHNICAL DESIGN GUIDELINES' (WATER BY DESIGN).
  2. FILTER MEDIA SPECIFICATION SHALL BE IN ACCORDANCE WITH THE 'ADOPTION GUIDELINES FOR STORMWATER BIOFILTRATION SYSTEMS (CRC FOR WATER SENSITIVE CITIES) AND THE BIORETENTION TECHNICAL DESIGN GUIDELINES (WATER BY DESIGN). BIORETENTION HYDRAULIC CONDUCTIVITY SHALL BE IN ACCORDANCE WITH PRACTICE NOTE 1: IN SITU MEASUREMENT OF HYDRAULIC CONDUCTIVITY' (FAWB). THE NUMBER OF SAMPLES TO BE TESTED SHALL BE IN ACCORDANCE WITH THE 'CONSTRUCTION AND ESTABLISHMENT GUIDELINES - SWALES, BIORETENTION SYSTEMS AND WETLANDS' (WATER BY DESIGN).
  3. CONSTRUCTION TOLERANCES SHALL BE IN ACCORDANCE WITH THE 'CONSTRUCTION AND ESTABLISHMENT GUIDELINES - SWALES, BIORETENTION SYSTEMS AND WETLANDS' (WATER BY DESIGN)
  4. TRANSITION LAYER AND DRAINAGE LAYER DEPTHS VARY WITH DESIGN. DEPTHS AND SPECIFICATION TO BE IN ACCORDANCE WITH PROJECT DRAWINGS AND THE 'BIORETENTION TECHNICAL DESIGN GUIDELINES' (WATER BY DESIGN)
  5. UNDERDRAIN TO BE SLOTTED RIGID PIPE LAID AT 0.5% GRADE. REFER TO PROJECT DRAWINGS FOR DIAMETER AND PIPE INVERT. PIPE SHOULD NOT BE INSTALLED WITH A FILTER SOCK SURROUNDING PIPE. UNDERDRAIN PIPES SHALL BE SEALED INTO PITS USING GROUT OR OTHER APPROVED WATERTIGHT SEAL.
  6. LINER (AS SPECIFIED ON THE PROJECT DRAWINGS):
    - 6.1. PERMEABLE LINER: NON-WOVEN GEOTEXTILE FILTER CLOTH TO BASE AND SIDES OF BIORETENTION SYSTEM. FILTER CLOTH NOT TO BE PLACED BETWEEN ANY FILTER LAYERS. REFER 'BIORETENTION TECHNICAL DESIGN GUIDELINES' (WATER BY DESIGN)
    - 6.2. IMPERMEABLE LINER: COMPACTED CLAY OR SYNTHETIC LINER WITH PERMEABILITY OF NO GREATER THAN  $1 \times 10^{-9}$  m/s. IMPERMEABLE LINER TO BE SEALED AROUND ALL PROTRUSIONS. SYNTHETIC LINERS TO BE INSTALLED AND SEALED IN ACCORDANCE WITH MANUFACTURERS REQUIREMENTS. REFER 'BIORETENTION TECHNICAL DESIGN GUIDELINES' (WATER BY DESIGN).
  7. UNDERDRAIN OUTLET RISER ESTABLISHES MAX SATURATED ZONE WATER LEVEL. UNDERDRAIN OUTLET RISER AS PER PROJECT DRAWINGS AND 'BIORETENTION TECHNICAL DESIGN GUIDELINES' (WATER BY DESIGN)
  8. VEGETATED BATTER. SLOPE AND PLANTING TO BE IN ACCORDANCE WITH PROJECT DRAWINGS AND 'BIORETENTION TECHNICAL DESIGN GUIDELINES' (WATER BY DESIGN).
  9. INSPECTION/CLEANOUT POINT. VERTICAL SOLID PIPE SECTION ATTACHED TO THE END OF EACH UNDERDRAIN IN ACCORDANCE WITH PROJECT DRAWINGS AND THE 'BIORETENTION TECHNICAL DESIGN GUIDELINES' (WATER BY DESIGN)
  10. FILTER CLOTH TO BE FIXED TO PERIMETER OF PIT TO AVOID RUNNELLING OF WATER BETWEEN PIT AND SOIL INTERFACE. BEGIN FILTER CLOTH 100 ABOVE SURFACE. EXTEND TO 100 BELOW SURFACE. CONTINUE 300 HORIZONTALLY INTO FILTER MEDIA.

- ESTABLISHMENT NOTES:**
1. BASIN DRAINAGE LAYERS AND FILTER TO BE CONSTRUCTED AND TEMPORARILY PROTECTED USING GEOTEXTILE PLACED OVER FILTER WITH 75mm TOPSOIL AND TURFED PRIOR TO CIVIL ON-MAINTENANCE. BASIN TO BE KEPT IN THIS PROTECTED STATE FOR A 24 MONTH MAINTENANCE PERIOD TO ALLOW FOR SUBSTANTIAL CONSTRUCTION WORK.
  2. PRIOR TO OFF MAINTENANCE INSPECTION, 3 IN-SITU FILTRATION TESTS ARE TO BE PROVED DEMONSTRATING THAT THE HYDRAULIC CONDUCTIVITY IS MET AT 200mm/hr.
  3. PLANTING OF FILTER TO OCCUR ONLY AFTER SUCCESSFUL INFILTRATION TESTS AND COUNCIL ACCEPTANCE OF CIVIL WORKS 'OFF MAINTENANCE'. PLANTING ON FILTER SUBJECT TO FURTHER 12 MONTHS MAINTENANCE PERIOD.

**NOTE:**

1. FOR DESIGN AND CONSTRUCTION NOTES REFER TO IPWEA STANDARD DRAWING DS-078.
2. DRAWINGS TO BE READ IN CONJUNCTION WITH SITE BASED STORMWATER MANAGEMENT PLAN AND LANDSCAPE ARCHITECT'S PLANS

REV	DATE	DESIGN	DRAWN	REVISION DETAILS	DRAWN	STATUS	 ENQUIRIES@PEAKURBAN.COM.AU	SCALE 1:20 0.2 0.4 0.6 0.8 1 A1 1:40 A3 1:50 1 0.5 0 1 2 A1 1:100 A3	CLIENT <b>RIPLEY PROJECTS PTY LTD</b>	PROJECT NAME <b>HAYFIELD STAGE 5</b> 352 RIPLEY ROAD RIPLEY	DRAWING TITLE <b>BIO RETENTION TYPICAL NOTES, SECTIONS AND DETAILS</b>
1	27.04.20	AS	AS	FOR APPROVAL	AS	NOT FOR CONSTRUCTION					
2	16.06.20	AS	AS	FOR APPROVAL	MH	APPROVED ANDREW NGO RPEQ 12329	ASSOCIATED CONSULTANT SURVEYOR: SURVEY MARK PH: (07) 3188 9020	PROJECT No. 17-0195	DRAWING No. 202	REVISION 2	