





SWIFT

| AREA CALCULATIONS | |
|-------------------|-----------------------------|
| | SQM |
| GROUND FLOOR | 140.49 |
| GARAGE | 36.08 |
| ALFRESCO | 10.15 |
| PORCH | 1.60 |
| | 188.32 m² |

PRE-CONSTRUCTION

- HIA fixed site works.
- Plans - Specifications.
- Engineers soil report & slab design.
- Council building application fees.

SITE WORKS FOUNDATIONS & CONNECTIONS

- Site scrape and/or balanced cut & fill
- excavation for up to 1500mm site fall over the building platform.
- Engineer designed concrete slab to suit up to
- "H2" slab with bulk concrete piercing.
- (up to and including a depth of 600mm).
- Termite treatment to slab penetrations and physical perimeter barrier.
- Sewer & storm water connections to existing serviceable connection points for sites up to 600m² in size with a standard 6 meter set back from front boundary (battle-axe, other odd shaped blocks and blocks where service connection exceeds standard allowances may incur extra service costs).
- Eight (8) meters plan length of electrical mains.
- Water connection from pre-tapped water main up to and including six (6) meter setback to house.
- House constructed for "N2" wind rating conditions (W33).
- No allowance is made for retaining walls.

ENERGY EFFICIENCY

- Bulk ceiling insulation, rating R2.5, to ceiling area.
- Double sided foil wall-wrap to external stud walls.
- Energy efficient aluminium improved windows and sliding door units
- Weather stripping to hinged external doors.
- Electric hot water system.
- 500 KPA water pressure limiting device.
- LED down-lights.
- Approximately 1.8kw solar power system.

BRICKS, WINDOWS, ROOFING AND GARAGE

- Colorbond roof.
- Colorbond fascia & gutter from the standard builders' range of colours.
- Select range of clay bricks from the builder's standard range.
- Natural mortar.
- Powder coated aluminium windows from the standard builders' range of colours, with obscure glass to wet areas.
- Keyed window locks to all opening sashes and sliding doors.
- Auto Sectional garage door to garage from the standard builders' range of colours and two (2) handsets.

KITCHEN INCLUSIONS

- 20mm manufactured stone benchtops.
- Laminate finish cupboards from the standard builder's range of laminates.
- Door handles from the standard builder's range.
- 600mm under-bench oven.
- Laminate finish microwave oven provision to cabinetry.
- Electric ceramic 600mm cooktop.
- Freestanding stainless-steel dishwasher.
- Stainless steel 600mm slide-out rangehood.
- 1¾ bowl stainless steel kitchen sink.
- Chrome sink mixer.
- Cold water-point to fridge space for an ice maker.
- Bulkhead above kitchen overhead cupboards.

BATHROOM ENSUITE AND TOILETS

- Wall-hung vanities with laminate bench tops from the standard builder's range of laminates.
- Door handles from the standard builder's range.

DISCLAIMER: HTCB QLD reserve the right to alter any of the above inclusions due to continuing product development or availability of items.

Initial _____



- Clear laminated glass shower screens with powder coated aluminium frames from the standard builder's range of colours.
- White acrylic bath.
- 900mm high polished edge mirrors fitted to the same width as the vanity unit.
- Chrome mixer tapware, double towel rails and toilet roll holders.
- Vitreous China close coupled toilet suites.
- Semi-inset basins (or semi recessed as required).
- Shower on rail to bathroom and ensuite showers.

CERAMIC TILING

- Bathroom & ensuite floors, and
- 2000mm high to showers,
- 600mm above bath (nominal),
- 200mm skirting tile.
- Kitchen tiled splashback:
- 600mm high off bench.
- Toilet & Laundry floors and,
- 400mm splash back over tub
- 200mm skirting tiles
- No allowance has been made for frieze or decorator tiles.
- No allowance has been made for laying of border tiles, 45-degree patterns or floor feature tile layouts.

ELECTRICAL

- Earth leakage safety switch & circuit breakers.
- Single phase underground power connection from existing supply point.
- Meter box will be installed on the side nearest to the mains connection point.
- One (1) double power point to each room and as per electrical plan.
- One (1) 240-volt downlight point to each room as per electrical plan.
- Two (2) external para flood light points.

- Two (2) television points complete with 5 lineal meters of cable and no antenna.
- Smoke detectors hard wired with battery backup.
- Pre-wiring for two (2) Telstra phone points.
- Exhaust fan to bathroom and ensuite.
- Single GPO to microwave oven provision in kitchen.
- USB/double power point to the end of kitchen cabinetry.

STANDARD INTERNAL AND EXTERNAL FEATURES

- 2550mm ceiling heights throughout (ground level only in 2 storey homes).
- Round aluminium powder-coated handrail and vertical balustrade to external balcony as selected from builders' standard range where applicable.
- Paint grade front door with clear glazing.
- Paint grade hinged doors to other external doors if applicable.
- Paint grade flush panel internal passage doors.
- Magnetic door stops from builders' standard range to passage doors.
- Vinyl sliders from builders' standard range to wardrobe doors.
- Builders range exterior leverset to front door
- Interior leverset to internal doors.
- 90mm paint grade coved cornice.
- 41mm paint grade splayed architraves.
- 67mm paint grade splayed skirting.
- Paint:
 - Three (3) coat internal paint system - 2 colours allowed i.e. 1 colour to wall and 1 colour to timber work,
 - Two (2) coats to ceiling to Paint
- Manufacturers standard specifications,
- Two (2) coat external paint system to external trim and doors to paint manufacturers standard specifications.
- 45 ltr laundry trough and cabinet.
- Two (2) external garden hose taps.

DISCLAIMER: HTCB QLD reserve the right to alter any of the above inclusions due to continuing product development or availability of items.

Initial _____



- .AAA rated water saving shower heads and tap- ware.
- .Internal & external builders house clean and site clean after construction.
- .Carpet grade staircase with painted timber balustrade for staircases as selected from builders' standard range.

WARRANTIES

- .Statutory maintenance period.
- .Statutory structural guarantee period.

TURN KEY PACKAGE

PRE-CONSTRUCTION

- .Provide additional council cross over and building application fees according to local city council.

SITE WORKS

- .Provide additional driveway cut excavation including kerb cut-out and removal when non-mountable kerb exists.

WINDOWS

- .Powder coated aluminium diamond grill security screens.
- .Powder coated frames to glass sliding doors.
- .Powder coated frames to opening windows.

LANDSCAPING

- .Provide up to 70 lineal meters of 1800mm high

- treated pine timber fencing.
- .Provide (1) steel frame gate with treated pine palings.
- .Provide up to 60 m2 of exposed aggregate driveway, front path and porch.
- .Provide up to 300 m2 of A-Grade turf.
- .Provide one (1) 15m2 garden bed including clay paver edge, builders' range plants and mulch.

INTERNAL & EXTERNAL FEATURES

- .Provide carpet to all bedrooms and living rooms as selected from the builders' standard range.
- .Provide main floor tiles to all other internal areas (excluding garage).
- .Provide suitable external grade tile finish to alfresco slab as selected from the builders' standard range.
- .Provide a fold down wall mounted clothes line as selected from the builders' standard range.
- .Provide a TV antenna and booster (as required) to roof as selected from the builders' standard range.
- .Provide a letter box as selected from builders' standard range.
- .Provide Roller blinds throughout. (Excluding Wet Rooms)
- .Provide (1) white fan/light to all bedrooms.
- .Provide (1) split system A/C from builders' standard range to living room and (1) to master bedroom.
- .Provide internal & external builders house clean.

Name _____ Signature _____ Date _____

Name _____ Signature _____ Date _____

Name HTCB QLD Signature _____ Date _____

DISCLAIMER: HTCB QLD reserve the right to alter any of the above inclusions due to con-tinuing product development or availability of items.

